

SAMPLE

BID SCHEDULE

HAPPY WATERSHED, SITE NO. 3-4A

ITEM #	WORK OR MATERIAL	SPEC. #	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1.	Seeding, Mulching & Fertilizer	6	10.7	Ac.	\$ _____ \$ _____	
2.	Mobilization	8	Lump Sum		\$ _____ \$ _____	
3.	Water	10	1300	M. Gal.	\$ _____ \$ _____	
4.	Excavation, Common	21	10,450	Cu. Yds.	\$ _____ \$ _____	
5.	Earthfill, Embankment	23	69,500	Cu. Yds.	\$ _____ \$ _____	
6.	Earthfill, Hand Compacted	23	Lump Sum		\$ _____ \$ _____	
7.	Earthfill, Misc.	23	Lump Sum		\$ _____ \$ _____	
8.	Earthfill, Random	23	8,354	Cu. Yds.	\$ _____ \$ _____	
9.	Drainfill	24	25	Cu. Yds.	\$ _____ \$ _____	
10.	Reinforced Concrete (Class 4000)	31	15.7	Cu. Yds.	\$ _____ \$ _____	
11.	Steel Reinforcement	34	500	Lbs.	\$ _____ \$ _____	
12.	Reinforced Concrete Pipe, 24" Diameter	41	184	LF	\$ _____ \$ _____	
13.	Reinforced Concrete Pipe (Riser, 36" Diameter, W/Tees)		41	Lump Sum	\$ _____ \$ _____	
14.	CMP, 12" Diameter	44	42	LF	\$ _____ \$ _____	
15.	Trash Rack	81	Lump Sum		\$ _____ \$ _____	
16.	Special Area Fences (Smooth Wire)	92	5,000	LF	\$ _____ \$ _____	
17.	Knife Gate Valve, 10" Diameter	208	Lump Sum		\$ _____ \$ _____	
18.	Rock Riprap Around Inlet	212B	11	Tons	\$ _____ \$ _____	
19.	Plastic Drainage Pipe, 4" Diameter	220	74	LF	\$ _____ \$ _____	
20.	Corrugated Metal Pipe, 36" Diameter	56	51	LF	\$ _____ \$ _____	
Total Bid					\$ _____	

Contractor _____
Signature